MAHANADI COALFIELDS LIMITED

OFFICE OF THE GENERAL MANAGER
LINGARAJ AREA,P.O.: DEULBERA COLLIERY
DIST. ANGUL (ORISSA) – 759 102

01	Name of the work	Repair and maintenance of road from NH to Ranipark water loading point under Lingaraj Area. (Item No.03)
02	Place of work	Lingaraj Area.
03	Tender Notice No. & date	GM(LA)/Tender/SO(C)/2021-22/419 dtd.04.06.2021
04	Sanction Estimate cost	Rs. 1,86,016.11 only
05	Cost of application fee	Not Required
06	Cost of Earnest money	Not Required
07	Date of issue of tender documents	From 10.06.2021 TO 12.06.2021
08	Date and time of submission of tender in prescribed tender box.	Upto 1.00 PM on 14.06.2021.
09	Date and time of opening of Tender documents i.e. Part-I & Part-II (Tech. Bid & Price Bid).	Dt.16.06.2021 at 11.00 PM
10	Name & address of the company issuing tender.	MCL, Lingaraj Area.
11	All the terms and conditions prevalent in MCL in connection with the contract will hold good to you.	

04/6/21

STAFF OFFICER(C)
LINGARAJ AREA.

Scanned by CamScanner

4

SUB: Schedule of quantity for the work "Repair and maintenance of road from NH to Raniark water loading point under Lingaraj Area"

Sl. No.	Description	Qnty	Unit	Rate	Amount	Ref.
1	2	3	4	5	6	
1	Supplying and stacking at work site hard granite or equivalent as approved by EIC, hand broken stone metal 90mm to 45mm size i.e. IRC GR-I of approved quality including screening & stacking along road side equidistantly and uniformly including royalty, octroi, and all other taxes complete with all leads and lifts (A deduction of 7.5% is to be made on account of voids in stone metal. Measurement of material is to be taken just before laying work starts and payment shall be made only after laying of the material)	84.99	Cum	1080.35	91818.95	Road SOR 2018 MCL-17
2	Laying Gr-I (90mm-45mm) or Gr-II (63mm-45mm) metal in WBM sub base course i/c screening, sorting, spreading to template, packing with smaller stones, blinding with moorum, watering and consolidation with power roller-80/100 KN capacity i/c hire charges and running cost of road roller, pay of driver, khalasi & chowkidar and providing proper signals, road barriers etc. complete but excluding the cost of material like stone metal, packing stone and moorum (Payment to be made for compacted volume of WBM layer actually laid). For estimation purpose, loose quantity of stone metal for 1 cum. compacted volume of WBM will be 1.221 cum i.e. 1.00 cum + 32% for looseness factor - 7.5% for void = 1.221 cum)	69.60	Cum	503.35	35033.16	Road SOR 2018 MCL-22
3	Supplying and stacking good quality moorum at work site with all lead and all taxes, duties and royalty all complete.	53.40	Cum	418.50	22347.90	Road SOR 2018 MCL-15
4	Spreading moorum/sand/ stone dust etc. in layers not exceeding 150mm in thickness, levelling to required gradient and camber, watering and consolidation of each layer with power roller 80/100 KN capacity (Payment to be made for compacted volume of the moorum/sand).	30.63	Cum	275.55	8440.10	Road SOR 2018 MCL-23(a)
	Total Estimated Cost				**157640.11**	
	Add 18% GST				**28376.00**	
	Total Estimated Cost				**186016.11**	

Tenderer should quote percentage rate only. The rate quoted in figures and words

I will execute the above work @ _____% including GST (In words_____ above/below the estimated cost

NB: You are requested to select (write in the bottom) the GST category you belong to as per list given below:

1. Goods and Services Tax(GST) Status of Bidder(Not Applicable for Exempted Goods /Services)

The bidder should be either

GST Registered Bidder/Dealer OR GST unregistered Bidder/Dealer

TENDERER

Staff Officer (Civil)
Lingaraj Area

Scanned by CamScanner