Bill of quantity for the work " Regular maintenance of lawns, gardens beds, plants of Project Office BOCM of Lakhanpur Area".

Sl.No.	Ref no.	Description	Qnty.	Unit	Rate	Amount
1	AR	**Regular maintenance of lawns, gardens, flower beds, plants of Project Office, BOCM of Lakhanpur Area.**				
		SCOPE OF WORKS:				
		(a) Contractor shall maintain existing lawns, flower beds, plants garden area.				
		(b) Contractor will prepare new lawns, flower beds & gardens as and when required by digging, excavating and levelling the ground as per instruction of EIC.				
		(c) Contractor shall be responsible for planting new plants like hedges, saplings, seasonal flowers etc. by digging pits and maintaining the same (Cost of the plants to be paid separatly to the agency.)				
		(d) Contractor shall arrange at his own cost all necessary tools like spade, khurpi, pick-axe, secateures, hedge cutter, grass cutter, sickle tins & jhuri bhars, pipes etc in suffucient numbers as directed by EIC.				
		(e) The fertilisers, manures,pesticides etc. are to be applied in the lawn, garden as and when required. (The cost of fertlizers, manures, pesticdes etc. shall be paid separatly to the agency).				
		(f) Water will be made available at some points by the department and the contractor will use the water by using pipes which will be procured by the contractor.	Per day	165		
		(g) The pump set for raw water will be operated and used by the contractor. The pump in working condition will be handed over to the contractor, which shall be returned to the department in working condition on expiry of contract. The pump is to be maintained by the contractor.				
		(h) Maintenance work as desired by EIC on priority basis has to be strictly followed by the contractor.				
		(i) The lawn area, garden area is to be kept clean from rubbish, weeds and jungles. The uprooting of rank vegetation in the lawn area is to be done fortnightly in monsoon period and monthly in rest period. The cutting of grass in lawn area is to be done once in a month.				
		(j) The cutting of the hedges is to be done once in a month and the trimming of tree/plant will be done in every 03 months.				
		(k) Total area to be maintain per day=10566.00 sqm. For this in the analysis 10.75 nos. Of manpower (8.5 unskilled, 1.75 Mali & 0.5 pump operator) has been adopted.				
		Total				
		Add GST @ 18% only				
		Total				

PE(Civil),BOCM

1-Please quote item rate for item no.1

2-Rate must be quoted in figures as well as in words also.

3-I have gone through the terms and conditions kept in the office of the PE(C),BOCM and will abide.

Signature of Bidder with Seal & date